

+44 (0) 1270 753 000


uk@flowcrete.com

@flowcreteuk



CONTACT THE FLOORING SPECIALIST





This project exemplifies the ability of resin flooring manufacturer Flowcrete UK and specialist coatings contractor Total Protection to provide clients with every product and service required for a large-scale social housing flooring project. This holistic approach includes identifying existing issues and delivering a complete package throughout pre-contract specification and inspection to post-contract maintenance and warranty.

The site in Newtown consists of a 45-unit garage as well as a two-storey car park and ramp. The garages are rented to local council tenants and are in constant use.

When Flowcrete UK and Total Protection reviewed the 1,580 m² site a number of issues were recorded, including water migrating from the car park's top deck to the lower deck, cracking, leaking gullies and undulations in the concrete slab causing ponding. One of the main problems in the garage area was that a 100 ml recess in the concrete slab's centre was collecting water.

Cambridge Council could source all of the various repair mortars, screeds, damp proof membranes, PU injection systems, corrosion protection and resin coatings as well as the multidisciplinary knowledge required to fix the existing problems and upgrade the site directly from Flowcrete UK and Total Protection.

This was a significant factor behind the council choosing this supplier and applicator partnership, as it meant that the client did not have to spend time and resources finding a number of different manufacturers and contractors for each aspect of the project.

The Managing Director of Total Protection Ltd, Nick DiCienzo, said: "This project really showcases the benefits of our partnership with Flowcrete UK for the South's social housing sector, as this was a difficult task that required a wealth of specialist knowledge as well as multiple high performance products.


"We always have the needs of the tenants in mind when we undertake any application. We know that the work has to be completed quickly to avoid disruption to the tenant's day-to-day lives — but the quality also has to be there in regards to what systems are used and how they are applied, in order to ensure that the floor provides many years of reliable, effective use."

Flowcrete UK's Managing
Director, Kevin Potter, said:
"We're excited to be working in
partnership with Total Protection,
as it means that we can offer
an exceptional service to social
housing developments carrying
out a new-build or refurbishment
flooring project.

"Previously specifiers and developers would need to spend time assembling a variety of different suppliers and contractor teams before they could embark on a project such as the one at Newtown, however our new partnership avoids all this hassle, streamlining the route to a high quality floor finish."

The combination of Flowcrete
UK products used during this
project included Flowfast F1
Mortar to bring the substrate up
to standard, repair the gullies
and infill voids and buried joints.
Isocrete Isopol SBR created a
waterproof screed on the car park
ramp and main garage area as
well as a waterproof render band
around the perimeter of the walls
and Isocrete M-Bond primer was
applied to protect against rising
moisture in the garage area.

Flowcoat SF41, a hard wearing epoxy resin coating, was applied as a wearing surface across the 850 m² garage, with anti-slip aggregates incorporated into the finish. 700 m² of the fast cure deck coating system Deckshield Rapide ID-HD was installed on the car park's top deck and ramp to create a robust surface able to withstand traffic, weather and automotive chemicals.





"Flowcrete Group Ltd" uk@flowcrete.com

